



**भारत अन्न - भारतीय तेल ताड़ अनुसंधान संस्थान**  
**ICAR-Indian Institute of Oil Palm Research**  
क्षेत्रीय अनुसंधान केन्द्र, पालोड, पच्चा ( P.O ),  
Regional Station, Palode, Pacha (P.O),  
तिरुवनंतपुरम- 695562, केरल, भारत  
Thiruvananthapuram – 695562, Kerala, India



F.No.422/2017

Dated: 05.03.2018

**Tender Notice**

Sealed tenders are invited under single cover system from contractors satisfying the eligibility criteria for the work of **providing GI sheet roofing (colour coated) over the Administrative Block of IIOPR RC Palode.**

<b><u>SL. No</u></b>	<b><u>Work Description</u></b>	<b><u>Approx Area</u></b>	<b><u>Lump sum Amount in Rs.</u></b>
1.	Chipping off the old plaster on the parapet wall and replastering with cement plaster.	20 m <sup>2</sup>	
2.	Laying cement concrete in retaining walls	1.5 m <sup>2</sup>	
3.	Providing and fixing pre coated GI sheet of specification provided and making of truss work with round, square, rectangular hollow GI tubes with all works and painting complete	320 m <sup>2</sup>	
4.	Constructing a staircase canopy for rain protection for the staircase to upper floor with complete work. Gutter pipe painting etc.	30 m <sup>2</sup>	

**The tender should confirm to the following conditions**

1. The tender should reach the undersigned on or before **15.03.2018**.
2. Tenders received through CPP Portal with digital signature only will be accepted.
3. Work should be completed within a period of 3 months from the receipt of work order.
4. The tenderer should have successfully completed similar work in the past 5 years (as on 05-03-18). (Documentary proof of the above may be attached if available)
5. Only materials from ISO certified companies are to be used for the work.
6. The amount quoted by the tenderer shall be inclusive of all costs such as labour, material, equipment, rental, and transportation charges.
7. Tenderer is advised to inspect the site before quoting the rates.
8. The tenderer shall carry out the work without causing any disturbance to the regular functioning of the office.
9. If the tenderer is found to be using any material which is substandard than the required quantity, the officer in charge is at the liberty to stop the work and to take further actions. It is good that prior approval obtained for the quality of material before using them.



भारतअनूप - भारतीय तेल ताड़ अनुसंधान संस्थान  
ICAR-Indian Institute of Oil Palm Research  
क्षेत्रीय अनुसंधान केन्द्र, पालोड, पच्चा ( P.O ),  
Regional Station, Palode, Pacha (P.O),  
तिरुवनंतपुरम- 695562, केरल, भारत  
Thiruvananthapuram – 695562, Kerala, India



10. The bidding document should contain EMD amount of **Rs.10000/-** in form of Demand Draft in favour of "**ICAR Unit IIOPR**" payable at **Eluru, Andhra Pradesh**..However, the EMD of the unsuccessful bidder will be returned soon after the bidding is finalized.
11. The EMD of successful bidder shall be forfeited if the selected firm/contractor does not take up and/or complete the work within the time schedule or as per requirement
12. The right to accept or reject any or all the tenders in full or part thereof is reserved by the Scientist in Charge.
13. Scientist in Charge of this centre may be contacted for further details.
14. Photocopy of the PAN card must be submitted along with the bill, if selected.
15. If the Agency is registered with the labour office, a copy of which may please be enclosed for our reference

Scientist-in-charge



भाकरअनूप - भारतीय तेल ताड़ अनुसंधान संस्थान  
ICAR-Indian Institute of Oil Palm Research  
क्षेत्रीय अनुसंधान केन्द्र, पालोड, पच्चा ( P.O ),  
Regional Station, Palode, Pacha (P.O),  
तिरुवनंतपुरम- 695562, केरल, भारत  
Thiruvananthapuram – 695562, Kerala, India



Annexure-I

Sl No	Schedule of specification
1.	Pre coated GI profile sheets with Zinc coating 120 gm in 240 mpa grade steel 25 microns Epoxy primer Polyester Top Coat 15-18 microns.(TATA 0.35/JSW 0.45)
2.	Providing and laying cement concrete 1:1 $\frac{1}{2}$ :3 stone aggregate 20mm.
3.	Plastering with plaster mix of 1:3 in 6 mm thick on parapet wall and concrete structure to give even finish.
4.	Priming and painting with synthetic enamel paint @ 1.60 to 2 ltr /10 m <sup>2</sup> primer @2-2.20 kg/10 m <sup>2</sup>
5.	Steel work for tubular truss (square, round or rectangular hollow tubes) GI 15 cm - 10cm, 5 cm, 3.75 cm for pillars, puritas, rafters and truss respectively. (B class, ISI grade)
6.	The roof work should be complete in all respect and additional requirements if any other than above may be included.

Amount quoted should be inclusive of all type of taxes & cess.